

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19617-00-00  
Spot: SWSWNWSW Sec/Twnshp/Rge: 9-25S-5E  
1624 feet from S Section Line, 5280 feet from E Section Line  
Lease Name: WILSON A Well #: 249  
County: BUTLER Total Vertical Depth: 2484 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2100		
COND	10.75	90		
PROD	4.5	2439		175 SX
SURF	7	2411		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2014 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA  
MAR 12 2015

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/11/2014 5:00 PM KCC Agent: DUANE KRUEGER

RECEIVED

Actual Plugging Report:

RIH W/TBG @ 650', CIRCULATED HOLE CLEAN, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 4% CC & DISPLACED IN CASING. PULLED TBG @ 350', REVERSED CIRCULATED CEMENT OUT OF HOLE. WAITED 2 HORUS, TAGGED CEMENT @ 395'. PRESSURED CASING @ 200#, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES 270'-271' (4 HOLES). SWEDGED INTO 4.5" CASING, WELL WOULD NOT CIRCUALTE. CEMENT ON BACKSIDE OF 4 1/2". RIH W/ TBG @ 270', CONSODLIDATED MIXED & PUMPED 45 SXS 60/49 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CONSOLIDATED CEMENT TICKET # 48435.

Perfs:

Top	Bot	Thru	Comments
2440	2476	CSG	
2411	2427	CSG	
1520	1532	CSG	
664	684	CSG	

Remarks: 4 1/2" CIPB @ 1400'  
Plugged through: TBG

MAR 04 2015 XM

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

14