

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20005-00-00

Spot: NESWNWSE

Sec/Twnshp/Rge: 17-28S-4E

1830 feet from S Section Line, 2180 feet from E Section Line

Lease Name: KIRPATRICK

Well #: 2

County: BUTLER

Total Vertical Depth: 2410 feet

Operator License No.: 5030

Op Name: VESS OIL CORPORATION

Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

CIBP	7	2008		
------	---	------	--	--

PROD	7	0		0 SX
------	---	---	--	------

PROD	7	2409		
------	---	------	--	--

SURF	10.75	0		0 SX
------	-------	---	--	------

SURF	10.75	200		
------	-------	-----	--	--

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/28/2015 8:00 AM

Plug Co. License No.: 32991

Plug Co. Name: SIMMONS WELL SERVICE, INC.

Proposal Revd. from: CASEY COATS

Company: VESS OIL CORPORATION

Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA

MAR 02 2015

RECEIVED

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/28/2015 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1930', CIRCULATED HOLE CLEAN, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1738'. RIH W/TBG @ 1000', CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT PLUG @ 686'. TESTED CASING @ 300#, HELD OK. RIH ON WIRELINE @ 275' SHOT SQUEEZE HOLES 275'-276' (4 HOLES). SWEDGED INTO 7" CASING, CONSOLIDATED MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #48327.

Perfs:

Top	Bot	Thru	Comments
1940	1950	CSG	

Remarks:

Plugged through: TBG

MAR 04 2015
CKM

District: 02

Signed

Duane Krueger
(TECHNICIAN)