

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-21152-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 33-25S-5E
3926 feet from S Section Line, 4727 feet from E Section Line
Lease Name: PIERPOINT A Well #: 114
County: BUTLER Total Vertical Depth: 2150 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	681		300 SX
SURF	8.625	251		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2014 11:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
MAR 02 2015
RECEIVED

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/11/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 695', CIRCUALTED HOLE CLEAN, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 72 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. PULLED TBG. SWEDGED INTO 5.5" CASING, CONSOLIDATED MIXED & PUMPED 24 SXS 60/40 POZMIX 4% GEL 2% CC. SIP 750#. CONSOLDIATED CEMENT TICKET #48436.

Perfs:

Top	Bot	Thru	Comments
608	616		

Remarks:

Plugged through: TBG

MAR 04 2015
CKM

District: 02

Signed

Duane Krueger
(TECHNICIAN)

134