

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-03419-00-00
Spot: SENWSW Sec/Twnshp/Rge: 24-11S-17W
1650 feet from S Section Line, 990 feet from W Section Line
Lease Name: COLAHAN A Well #: 8
County: ELLIS Total Vertical Depth: 3548 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15	70		CWC
PROD	5.5	3544		100 SX
SURF	8.625	1141		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2015 9:00 AM
Plug Co. License No.: 34266 Plug Co. Name: PRAIRIE HAWK WELL SERVICE LLC
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 885-8240

Proposed Plugging Method: Ordered 550 sx 60/40 pozmix 4% gel cement, 500 # hulls and 12 sx gel.
Alt I complete.
Cement squeezed at 965' - 1645' w/265 sx cement

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2015 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perf Tech perforated at 1100'. Checked visually and saw that 15" and 8 5/8" pipe were full of cement. Prairie Hawk Well Service ran in hole with tubing to 3410' and pumped 12 sx gel followed by 50 sx cement w/250 # hulls mixed in. Pulled tubing to 1643'. Rigged to tubing and pumped 170 sx cement w/250 # hulls mixed in to circulate cement to pit. Pulled tubing. Topped off with 20 sx cement. Hole standing full.

GPS: 39.07932 -099.16366
1709' FLS 4261' FEL
NW SE NW SW

Remarks: ALLIED CEMENTING TICKET # 055635

Plugged through: TBG

MAR 04 2015

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

FEB 25 2015

RECEIVED

FEB 13 2015