

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-079-20703-00-00
Spot: E2NWNESW Sec/Twnshp/Rge: 35-23S-2E
2970 feet from N Section Line, 1750 feet from W Section Line
Lease Name: M. HARMS Well #: 1
County: HARVEY Total Vertical Depth: 2825 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S RIVER RD PO BOX 729
OXFORD, KS 67119

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | | 2750 | | |
| PROD | 5.5 | 2825 | 1780 | 100 SX |
| SURF | 8.625 | 202 | | 120 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/05/2015 12:00 PM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: MIKE ANSTINE Company: WD SHORT OIL CO., LLC. Phone: (620) 218-1822

Proposed Plugging Method: AS PER KCC RULES & REGS

KCC WICHITA
MAR 02 2015
RECEIVED

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 02/06/2015 3:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

1) SET CIBP AT 2750' AND BAILED 2 SKS CEMENT ON TOP. 2) SHOT 5.5" CASING OFF AT 1780' AND PULLED. 3) RAN IN HOLE WITH TUBING TO 256' AND PUMPED 110 SKX OF 60/40 4% CEMENT AND CIRCUALTED TO SURFACE. 4) PULLED TUBING OUT, DUG OUT CASING, CUT AND CAPPED APPROX. 3' DOWN.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2766 | 2772 | CSG | |

Remarks: CEMENTING COMPLETED BY ELITE SERVICES, EUREKA, KS TICKET #2151

Plugged through: TBG

MAR 04 2015
CPM

District: 02

Signed Jonathan Hill
(TECHNICIAN)