

1 020762

5-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APl NUMBER 15-175-21,257-0000
NW NW SW, SEC. 10, T. 7 S, R. 32 W/X
2310 feet from S section line
330 feet from W & section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30444
Operator: Charter Production Company
Name & Address 142 N. Mosley
Wichita, KS 67202

Lease Name Pittman Well # 1
County Seward
Well Total Depth 6480 ^{210.6^e} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1529

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor J.W. Gibson Well Service Co. License Number 5866
Address P.O. Box 1383, Guymon, OK 73942-1383

Company to plug at: Hour: 8:30 a.m. Day: 25 Month: 5 Year: 19 94

Plugging proposal received from Tom Patten
(company name) J.W. Gibson Well Service Co. (phone) 405-338-0664

logs: 5 1/2" at 6480', TOC 3850', Perfs at 4485-88'
1st plug set CIBP at 4485' with 2 sx cement on top,
2nd plug pump 50 sx cement at 1560',
3rd plug pump 40 sx cement at 700',
4th plug pump 10 sx cement at 40 to -4'.

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 31 1994

Plugging Proposal Received by Glenn Barlow WICHITA, KS
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____
Operations Completed: Hour: 5 p.m. Day: 25 Month: 5 Year: 1994

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4485' with 2 sx cement on top,
2nd plug pumped 50 sx cement at 1560',
3rd plug pumped 40 sx cement at 700',
4th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used common cement by Gibson. Recovered 1580' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-6-94
INV. NO. 40536

Signed Glenn R. Barlow
(TECHNICIAN)