

1 030926

3-17-88

API NUMBER 15-175-21,010-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 SE SW, SEC. 9, T 34 S, R 32 W/E

960 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Lease Name Johnson Well # 1-19

Operator: Shepler & Thomas, Inc.

County Seward 211.25

Name & Address

P.O. Box 1162

Well Total Depth 6500 feet

Liberal, KS 67905-1162

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1581

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 17 Month: 3 Year: 19 88

Plugging proposal received from Gary Marshall

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2779' Anhydrite 1700'

1st plug at 1590' with 50 sx cement, 2nd plug at 780' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Alan Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 a.m. Day: 17 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement,

2nd plug at 780' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Water well plugged with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED
I did not observe this plugging.

DATE 3-25-88

Signed Alan Barlow (TECHNICIAN)

INV. NO. 20210