

To: 1 060659  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,876-000R  
C NE SW, SEC. 5, T 34 S, R 32 W/E  
1980 feet from S section line

TECHNICIAN'S PLUGGING REPORT

3300 feet from E section line

Operator License # 4549

Lease Name Light "L" Well # 1

Operator: Anadarko Petroleum Corp.  
Name & Address: P. O. Box 351  
Liberal, KS 67901

County Seward 211.58

Well Total Depth 6510 St. Louis feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1625

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 6:00 am Day: 21 Month: September Year: 19 85

Plugging proposal received from Jim Barlow

(company name) Anadarko (phone) 316-624-6253  
Elevation 2795'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1616'

1st plug at 2600' with 50 sx cement

2nd plug at 1600' with 50 sx cement

3rd plug at 800' with 50 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:00 am Day: 21 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2600' with 50 sx cement, 2nd plug at 1600' with 50

sx cement, 3rd plug at 800' with 50 sx cement, 4th & 5th plugs - solid birdge- hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx

cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

DATE OCT 03 1985

SEP 27 1985

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 10304

CONSERVATION DIVISION  
Wichita, Kansas

9-21