

1090986

STATE CORPORATION COMMISSION

API NUMBER 15-175-21,765 * 0000
70'N 70'W C NW SEC. 4, T 34 S, R 32 W

CONSERVATION DIVISION - PLUGGING SECTION 1250 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1250 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ALEXANDER "C" WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY SEWARD 107.90

OPERATOR LICENSE # 4549

WELL TOTAL DEPTH 3320 FEET

OPERATOR: ANADARKO PETROLEUM CORP. PRODUCTION CSG: SIZE 5 1/2 @ 3310' WITH 320 SX

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 5/8" @ 523' WITH 210 SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES LICENSE NUMBER 5287

ADDRESS PO BOX 1598, LIBERAL, KS 67905-1598

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 01 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JIM BARLOW

(COMPANY NAME) HALLIBURTON ENERGY SERVICES (PHONE) 316-624-3879

WERE:

1ST PLUG PUMP 2 HULLS & 50 SX CEMENT OVER PERFS. 2ND PLUG PUMP 25 SX CEMENT DISPLACE TO 1600'. CUT CASING AT 644'. 3RD PLUG PULL TO 574' CIRCULATE MUD. PUMP 50 SX CEMENT. 4TH PLUG PULL TO 43'. PUMP 15 SX CEMENT. STAYED FULL.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:30 PM DAY: 01 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG PUMP 2 HULLS & 50 SX CEMENT OVER PERFS. 2ND PLUG PUMP 25 SX CEMENT. DISPLACE TO 1600'. CUT CASING AT 644'. 3RD PLUG PULL TO 574'. CIRCULATE MUD. PUMP 50 SX CEMENT. 4TH PLUG PULL TO 43'. PUMP 15 SX CEMENT. STAYED FULL.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. RECOVERED 644' VOLUME 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED (WILL OBSERVE THIS PLUGGING.)

SIGNED (TECHNICIAN) FORM CP-2/3

DATE 2-10-99

INV. NO. 60628