

2-9-88 15-175-30029-0000

To: 1 020118
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #E-16,786
C SW NE, SEC. 19, T 34 S, R 32 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549

Lease Name Condit Unit Well # 7-1
County Seward 208.00
Well Total Depth 6400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1600

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 4 p.m. Day: 5 Month: 2 Year: 19 88

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 6399' PBD 6316' Perfs at 6284-92, 6279-81' Elevation 3811'
1st plug pump 2 sx hulls and 25 sx common cement to bottom,
2nd plug pump 30 sx cement at 2750',
3rd plug pump 50 sx cement at 1650',
4th plug pump 25 sx cement at 700', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5:15 p.m. Day: 9 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 1/2 sx hulls and 25 sx common cement to bottom,
pressured to 1200 psi, Mud between all plugs

2nd plug pumped 30 sx cement at 2750',
3rd plug pumped 50 sx cement at 1650',
4th plug pumped 25 sx cement at 700',
5th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2830' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

Signed Glenn R Barlow
(TECHNICIAN)

DATE 2-18-88

INV. NO. 19886 MAR 24 1988
2-9

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1988
02-17-88
CONSERVATION DIVISION
Wichita, Kansas