

2-12-88 15-175-30028-0000  
175-30028-00-00

To: 1 020119  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 9/7/65  
C. SW SW, SEC. 18, T 34 S, R 32 W/EX  
660 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Condit Unit Well # 6-1  
County Seward 207.55  
Well Total Depth 6386 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1588

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 12 Month: 2 Year: 19 88

Plugging proposal received from Doug Blair  
(company name) Sargent's Casing Pulling Service (phone) 316-624-8179

were: 4 1/2" at 6381' PBSD 6350' Perfs at 6262-80' Elevation 2801' GL  
1st plug pump 1 sx hulls and 25 sx cement to bottom,  
2nd plug pump 30 sx cement at 2595',  
3rd plug pump 50 sx cement at 1638',  
4th plug pump 25 sx cement at 700', 5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:30 p.m. Day: 12 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement to bottom (2/10/88),  
2nd plug pumped 30 sx cement at 2595', Heavy mud between all plugs,  
3rd plug pumped 50 sx cement at 1638',  
4th plug pumped 25 sx cement at 700',  
5th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2617' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED ~~XXXXXXXXXX~~ observe this plugging.

Signed Glenn R Barlow (TECHNICIAN)

DATE 2-18-88

INV. NO. 19885 MAR 24 1988  
2-12

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1988  
CONSERVATION DIVISION  
WICHITA, KANSAS