

To: 1031395  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-189-22,060-00-00

NE NE SW SW SEC. 19, T 34 S, R 35 W/EX

4-22

1250 feet from S section line  
4030 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Baughman G Well # 3

Operator: OXY USA Inc.

County Stevens 35.00

Name & Address P.O. Box 26100

Well Total Depth 735 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 306

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cheyenne Drilling Inc. License Number 5382

Address P.O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 10 a.m. Day: 22 Month: 4 Year: 1996

Plugging proposal received from Tad Davis

(company name) Cheyenne Drilling Inc. (phone) 316-277-2062

Work: Company was running 742' of used 8 5/8" surface casing. Casing parted at 306'. Fished on casing for 3 days, washout prevented overshot and washover pipe to get back on 8 5/8".

Company instructed to: perforate 8 5/8" at 685'-688' w/3 shots per foot, and at 500-503' w/3 shots per foot. Run in hole with drill pipe to 735' and pump 360 sx Class H cement, then pull drill pipe to 309' and circulate 185 sx cement to pit with drilling mud.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 10:30 p.m. Day: 22 Month: 4 Year: 1996

ACTUAL PLUGGING REPORT Perforated 8 5/8" at 685-688' and 500-503' with 3 shots per foot.

Ran in hole with drill pipe to 735', pumped 360 sx Class H cement (15.6 #/gal), then

pulled drill pipe to 309' and circulated 185 sx cement to pit with drilling mud.

Ran seven joints of 8 5/8" back in hole (306') and circulated cement to surface.

Left 8 5/8" full of cement.

Remarks: Used Class H cement by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED  
I hereby certify and warrant to observe this plugging.

DATE APR 29 1996

INV. NO. 45469  
4-22

Signed Steve Durrant (TECHNICIAN)

RECEIVED  
TECHNICAL SERVICES DIVISION  
APR 29 1996  
A 10:59