

195 R

To: 1 020021
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-20,855-0000
NE SE, SEC. 15, T 34 S, R 35
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Skinner C Well # 2

Operator: Cities Service Oil & Gas Corporation
Name & Address

County Stevens 219.28

P. O. Box 300

Well Total Depth 6747 St. Louis feet

Tulsa, OK 74102

Conductor Pipe: Size 13 3/8 feet 749

Surface Casing: Size 8 5/8 feet 1714

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Daco, Inc. License Number 6416

Address P. O. Box 3010, Borger, TX 79007

Company to plug at: Hour: 4:00 pm Day: 14 Month: July Year: 1986

Plugging proposal received from Jim Brown

(company name) Daco, Inc. (phone) 806-273-7321

were: 5 1/2" at 6747' PBTD 6000' Perfs at 6158-67'; 6172-76' Elevation 2982' Est. Anhydrite 1714'

- 1st plug CIBP at 6000'
- 2nd plug CIBP at 4440'
- 3rd plug at shoot off with 40 sx cement
- 4th plug at 1745' with 50 sx cement
- 5th plug at 900' with 40 sx cement
- 6th plug from 40-0' with 10 sx cement

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:00 am Day: 15 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug CIBP at 6000' with 2 sx cement, 2nd plug at 2797' with 40 sx cement, 3rd plug at 1765' with 50 sx cement, 4th plug at 807' with 50 sx cement, and 5th plug from 40' to surface with 10 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

Remarks: Daco used common cement. Good return on mud to pit. Recovered 2798' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-86

JUL 24 1986

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 14507

7-15