

To: 1031470
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

11-3

API NUMBER 15- 189-20,337-0002
150' W of
C SE, SEC. 10, T 33 S, R 38 W/X
1320 feet from S section line
1470 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351, Liberal, KS 67905-0351

Lease Name Gaskill A Well # 2
County Stevens 211.90
Well Total Depth 6520 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1697

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: _____ Day: 1 Month: 11 Year: 19 97

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

was: 4 1/2" at 6216' w/130 sx cement, PBD 5235', Perfs at 6001-30, 6049-62, CIBP at 5600';
Cement retainer at 6042'

- 1st plug pump 2 sx hulls and 20 sx cement on bottom,
- 2nd plug at freepoint with 35 sx cement, 3rd plug at 1710' with 50 sx cement,
- 4th plug at 600' with 40 sx cement, 5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11 a.m. Day: 3 Month: 11 Year: 19 97

- ACTUAL PLUGGING REPORT
- 1st plug pumped 2 sx hulls and 20 sx cement at 5190-5072',
 - 2nd plug at 2600-2500' with 35 sx cement,
 - 3rd plug at 1710-1560' with 50 sx cement,
 - 4th plug at 600-500' with 40 sx cement,
 - 5th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Sargent & Horton. Recovered 2625' of 4 1/2" casing.
If additional description is necessary, use BACK of this form.)

INVOICED

I (XXX / did not) observe this plugging.

DATE 11-14-97

INV. NO. 49490

Signed Steve Durrant (TECHNICIAN)