

1 020838 2-1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-21,763-0000

S/2 SW, SEC. 11, T. 33 S, R. 38 W/E

1270 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Ramey A Well # 2

Operator: Anadarko Petroleum Corporation  
Name:  
Address P.O. Box 351  
Liberal, KS 67905-0351

County Stevens 202.15

Well Total Depth 6220 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1692

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Anadarko Petroleum License Number 4549

Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 10:30 a.m. Day: 1 Month: 2 Year: 19 95

Plugging proposal received from Jack Tuman

(company name) Anadarko Petroleum (phone) 316-544-7240

were: 5 1/2" at 6219' w/150 sx cement, CIBP at 3550, 3215', PBD 6156, Perfs at 3122-40, 3169-75'

1st plug pump 2 sx hulls and 25 sx cement at perfs, pressure up,

2nd plug pump 40 sx cement at 1900',

3rd plug pump 50 sx cement at 1700',

4th plug pump 50 sx cement at 650', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5:15 p.m. Day: 1 Month: 2 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs, pressured to 800#,

2nd plug pumped 40 sx cement at 1900',

3rd plug pumped 50 sx cement at 1700',

4th plug pumped 50 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'. All plugs displaced with heavy mud.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1920' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 2-15-95

INV. NO. 42205

Signed Glenn R. Barlow (TECHNICIAN)