

To: 1 020430
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,378 - 0000 115 p
SW SW NE NW, SEC. 11, T. 33 S, R. 38 W/EX

4030 feet from S section line
3890 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Miller "N" Well # 1
County Stevens 198.57
Well Total Depth 6110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1679

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Anadarko Petroleum Corp. License Number 4549
Address P.O. Box 351, Liberal, KS 67905-0351

Company to plug at: Hour: 1 p.m. Day: 24 Month: 1 Year: 19 92

Plugging proposal received from Jack Tuman

(company name) Anadarko (phone) 316-544-7240

Work: 4 1/2" at 6109' w/480 sx cement, PBD 6075', Perfs at 6006-32', DV tool at 3122', pumped 450 sx to surface

1st plug set CIBP at 5950', run tubing, tag CIBP, pump 7' sx cement on top,

2nd plug pump 15 sx cement at 1800'-1600',

3rd plug pump 25 sx cement at 650',

4th plug pump 3 sx cement from 40-0'

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:45 p.m. Day: 24 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5950', ran tubing, tagged CIBP, pumped 7 sx cement on top,

2nd plug pumped 15 sx cement at 1800-1600',

3rd plug pumped 25 sx cement at 650',

4th plug pumped 3 sx cement from 40-0'.

4 1/2" cemented in solid at top.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE JAN 29 1992

Signed Glenn R Barlow (TECHNICIAN) RWZ

INV. NO. 34388

RECEIVED
KANSAS CORPORATION COM
JAN 28 1992
CONSERVATION DIVISION
WICHITA, KS