

15-129-00215-0000  
15-129-00215-00-00

1 050724

API NUMBER 15- Completed 4-13-51

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SW NW, SEC. 20, T 33 S, R 39 W/EX  
3080 feet from S section line  
4930 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5598

Lease Name Addington Well # 1-20

Operator: Pan Eastern Exploration Company  
Name & Address: P. O. Box 351  
Liberal, KS 67901

County Morton

Well Total Depth 2653 86.22 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 467

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 12:00 pm Day: 12 Month: December Year: 19 85

Plugging proposal received from Jack Taylor

(company name) Pan Eastern (phone) 316-624-6253

were: 7" at 2435' PBSD 2653' Perfs at 2435-2653' (5 1/2" perforated liner from 2435-2653')

Pump through 7" with mud between plugs

1st plug pump 1 sack hulls and 50 sx cement to bottom

2nd plug at 600' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 50' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 12:30 pm Day: 12 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 50 sx cement to bottom. 2nd plug at 600' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 50' -- cement to surface with 10 sx cement.

Remarks: No Recovery. Used common cement by Sargent's  
(if additional description is necessary, use BACK of this form.)

INVOICED

STATE CORPORATION COMMISSION Signed Richard W. Lacey  
(TECHNICIAN)

DATE DEC 27 1985

JAN 15 1986 DEC 27 1985

INV. NO. 11752 12-12