

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21567-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 21-33S-39W
2100 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: KU ENDOWMENT G Well Number: 1
County: MORTON Total Vertical Depth: 6532 feet

Operator License No.: 4549 Production Casing Size: 5.5 feet: 4699 WITH 90 SX CMT
Op Name: ANADARKO PETROLEUM CORPORATI Surface Casing Size: 8.625 feet: 1706 WITH 435 SX CMT
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380 #212²⁹

Well Type: GAS UIC Docket No: Date/Time to Plug: 09/05/2003 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS WITH 25 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 700' WITH 30 SX CMT.
PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/08/2003 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 4648'. PERFS AT 3200-18'. CIBP @ 4300'. PORT COLLAR @ 3304' WITH 70 SX CMT. PUMP 300# HULLS WITH 25 SX CMT. DISPLACE WITH MUD & PRESSURE TO 500#. SHUT IN. 1ST PLUG PULL OUT OF HOLE WITH 5 1/2" TO 1465'. PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 550'. LOAD HOLE & PUMP 30 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

RECEIVED
OCT 01 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1475' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 10-1-03
VV. NO. 2004060558

Form CP-2/3 ✓