

To: 1041000 9-15
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION .50'
130 S. Market, Room 2078
Wichita, KS 67202

15-189-21926-0000
API NUMBER 15-189-21,926
S. of C NW SEC. 22 T. 33 S. R. 39 W/E
3910 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Demuth B Well # 3
County Stevens 203.06
Well Total Depth 6248 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1699

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Border-Line, Inc. License Number 7840
Address: P.O. Box 1043, Ulysses, KS 67880-1043

Company to plug at: Hour: 8 a.m. Day: 15 Month: 9 Year: 19 95

Plugging proposal received from Jack Tuman
(company name) Anadarko Petroleum Corporation (phone) 316-554-7240

Work: 5 1/2" at 3469' w/160 sx cement, PBTD 3427', Perfs at 3195-99, 3103-3119'
1st plug pump 2 sx hulls and 25 sx cement to bottom,

RECEIVED
STATE CORPORATION COMMISSION

2nd plug at cut off with 35 sx cement,

SEP 20 1995

3rd plug at 1730' with 50 sx cement,

CONSERVATION DIVISION
Wichita, Kansas

4th plug at 600' with 50 sx cement, 5th plug at 40' with 10 sx cement

Steve Pfeifer
(TECHNICIAN)

Plugging Proposal Received by _____

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30 p.m. Day: 15 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom, displaced with mud,

2nd plug shot off at 1911', pumped 35 sx cement at 1866',

3rd plug pulled casing to 1730' and pumped 50 sx cement.

4th plug pulled casing to 600' and pumped 50 sx cement,

5th plug at 0-30' with 10 sx cement.

Remarks: Used Class H cement by Halliburton. Recovered 1911' of 5 1/2" casing.

INVOICED
(if additional description is necessary, use BACK of this form.)
(XXXX) did not observe this plugging.

DATE 9-25-95
INV. NO. 43580

Signed Stephen J. Pfeifer
(TECHNICIAN)