

No: 1040930 1-26
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 75' W SE SE, SEC. 5, T 34 S, R 25 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 025-21,126-~~6708~~
660 feet from S section line
735 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5418
Operator: Allen Drilling/Simmons & Assoc.
Name & Address: 6565 S. Dayton, Ste. 3800
Englewood, CO 80111

Lease Name Theis Well # 1-5
County Clark
Well Total Depth 5750 18.88 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 829

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 6 p.m. Day: 26 Month: 1 Year: 1995.

Plugging proposal received from Richard

(company name) Allen Drilling Co. (phone) 316-793-3582

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1065-1100'
1st plug at 1100' with 50 sx cement,
2nd plug at 840' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:30 p.m. Day: 26 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement,
2nd plug at 840' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 2-1-95
INV. NO. 42116

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1995
CONSERVATION DIVISION
WICHITA, KANSAS

EFFECTIVE DATE: 1-14-95

DISTRICT # 4

SEA7... Yes... No

State of Kansas 15-025-21,126-0000
NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date January 15, 1995
month day year

75^{Spot} W SE SE Sec 5 Twp 34 S. Rg 25. X East

OPERATOR: License # 5418
Name: Allen Drilling / (Simmons & Associates)
Address: 6565 S. Dayton #3800
City/State/Zip: Englewood, CO 80111
Contact Person: Doug Hoisington
Phone: 303-799-6660

660 feet from South/North line of Section
735 feet from East/West line of Section
SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Clark
Lease Name: Theis Well #: 1-5

Field Name: McKinney

Is this a Prorated/Spaced Field? yes X.. no

Target Formation(s) Mississippi

Nearest lease or unit boundary: 660'

Ground Surface Elevation: 2115 feet MSL

Water well within one-quarter mile: yes X.. no

Public water supply well within one mile: yes X.. no

Depth to bottom of fresh water: 250', 200'

Depth to bottom of usable water: 400'

Surface Pipe by Alternate: X... 1 ... 2

Length of Surface Pipe Planned to be set: 800'

Length of Conductor pipe required: NA

Projected Total Depth: 5900'

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

... well ... farm pond X.. other

DWR Permit #: NA

Will Cores Be Taken? yes X.. no

If yes, proposed zone: NA

CONTRACTOR: License #: 5418
Name: Allen Drilling Company

Well Drilled For: Well Class: Type Equipment:
... Oil ... Enh Rec ... Infield X. Mud Rotary
X. Gas ... Storage X. Pool Ext. ... Air Rotary
... OWD ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

If OWD: old well information as follows:
Operator: NA
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X.. no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 7/9/95

AFFIDAVIT

220' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1995
CONSERVATION

Pusher Richard

SPUD DATE 1-13-95 INIT. SD
LENGTH SURFACE PLANNED 800'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 829 CONDUCTOR
ANHYDRITE T-1065 B-1100 ELEVATION
(5632)

TD 5750 FORMATION Miss

RAN PIPE @ DV TOOL ALT II DONE
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1100' Ft. W/ 50 SX

1/2 Base Anhy. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 840 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN S.P. DATE 1-25-95

TYPE OF CEMENT 60/40 per 26 gel

TARTING TIME 6:00 (AM/PM) DATE 1-26-95

COMPLETION TIME 9:30 (AM/PM) DATE 1-26-95

EMENT COMPANY Allied

RECEIVED
STATE CORPORATION COMMISSION
JAN 30 1995