

TO: *R*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-21053-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 3-34S-25W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: HARDEN FARMS Well Number: 1-3  
County: CLARK Total Vertical Depth: 5850 feet

Operator License No.: 30029 Conductor Pipe: Size \_\_\_\_\_ feet:  
Operator Name: STANDARD OPERATING COMPA Surface Casing: Size 8.625 feet: 669 WITH 325 SX CMT  
Address: 100 S. MAIN STE 415 Production: Size 4.5 feet: 5624 WITH 100 SX CMT  
WICHITA, KS 67202 Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_ 190.13

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2000 9:30 AM  
Plug Co. License No.: 6547 Plug Co. Name: SARGENTS CASING PULLING SERVICE  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENTS CASING PULLING SER Phone: (316) 624-7455

Proposed Plugging Method: BOTTOM PLUG PUMP 1 SX HULLS & 20 SX CMT. 1ST PLUG AT 1200' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/02/2000 1:30 PM KCC Agent: HILTON HIXON

Actual Plugging Report:  
PERFS AT 5509-5519'. PUMPED 100# HULLS & 20 SX CMT. LOADED HOLE WITH MUD. 1ST PLUG SPOT 50 SX CMT AT 1200'. 2ND PLUG PULLED TO 700' AND SPOT 50 SX CMT. 3RD PLUG PUMP 10 SX CMT FROM 40' - 0'.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 2000

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 5000' OF 4 1/2" CASING. CONSERVATION DIVISION  
Plugged through: CSG Wichita, Kansas

District: 01 Signed Hilton Hixon  
(TECHNICIAN)

INVOICED  
DATE 11/14/00 NOV 08 2000  
INV. NO. 2001060972 *MP*  
Form *CSG*