

To: 1031332 6-12
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,497-0000
C NE SE, SEC. 2, T 34 S, R 25 W/E
1980 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6568

Lessee Name Klinger Well # 1-2

Operator: Kaiser-Francis Oil Company

County Clark

Name & Address P.O. Box 21468

Well Total Depth 5900 191.75 feet

Tulsa, OK 74121-1468

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 639

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 12 Month: 6 Year: 1995

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 4 1/2" at 5899' w/300 sx cement, PBTD 5895', Perfs at 5503-08, 5518-36'

1st plug set CIBP at 5450' with 2 sx cement on top,

2nd plug at 1150' with 50 sx cement,

3rd plug at 659' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3 p.m. Day: 12 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5450' and dumped 2 sx cement on top,

2nd plug at 1150' with 50 sx cement,

3rd plug at 659' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 4040' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOLVED
I hereby observe this plugging.

Signed Steve Durrant
(TECHNICIAN)

DATE 6-23-95

INV. NO. 42985

6-12

STATE CORPORATION COMMISSION
RECEIVED
JUN 15 1995
CLERK OF CONSERVATION DIVISION