

To: 1 051588
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-27

API NUMBER 15- 025-20,951-00-00 310 R

NE NE SW, SEC. 27, T. 34 S, R. 24 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 8802
Operator: Cobra Oil & Gas Corporation
Name
Address P.O. Box 1929
Woodward, OK 73802-1929

2310 feet from S section line
2970 feet from E section line
Lease Name Isenbart 27 Well # 1
County Clark 188.50
Well Total Depth 5800 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 735

Abandoned Oil Well Gas Well X Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 596, Liberal, KS 67905

Company to plug at: Hour: 10 a.m. Day: 27 Month: 10 Year: 19 92

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 5799' w/250 sx cement, PBDT 5768', Perfs at 5566-73, 5575-90'

1st plug set CIBP at 5380' and dump 2 sx cement on top,

2nd plug pump 50 sx cement at 1000', 3rd plug pump 50 sx cement at 760',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 p.m. Day: 27 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5380' and dumped 2 sx cement on top,

2nd plug pumped 50 sx cement at 1000',

3rd plug pumped 50 sx cement at 760',

4th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent's. Recovered 3800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I () () / () () observe this plugging.

DATE 11-13-92

INV. NO. 36744

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1992