

1 110061

6-16-87

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 025-20,984-0000

C W/2 SW, SEC. 24, T 34 S, R 24 W/E

1320 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9657

Lease Name Gabbert Well # 1-24

Operator: Quintana Petroleum Corporation

County Clark 188.50

Name & Address 1050 17th Street, Suite 400

Well Total Depth 5800 feet

Denver, CO 80265

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 801

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Brandt Drilling Company, Inc. License Number 5840

Address 105 South Broadway, Suite 920, Wichita, KS 67202

Company to plug at: Hour: 11 p.m. Day: 15 Month: 6 Year: 19 87

Plugging proposal received from Ray King

(company name) Quintana Petroleum Corporation (phone) 303-628-9211

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1911'

1st plug at 810' with 60 sx cement,

2nd plug at 40' with 15 sx cement,

3rd plug to circulate rathole with 15 sx cement,

4th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by SD

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None x

Operations Completed: Hour: 2:30 a.m. Day: 16 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 810' with 60 sx cement,

2nd plug at 40' with 15 sx cement,

3rd plug to circulate rathole with 15 sx cement,

4th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1987

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED  
If not observed this plugging.

DATE 6-22-87

INV. NO. 17293

6-16

Signed James R. Hays  
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date June 1 1987

API Number 15-025-20,984-0000

OPERATOR: License # 9657
Name: QUINTANA PETROLEUM CORPORATION
Address: 1050 - 17th Street, Suite 400
City/State/Zip: Denver, Colorado 80265
Contact Person: E. Scott Kimbrough
Phone: (303)628-9211

C... W/2 SW Sec. 24... Twp. 34, S, Rg. 24... X West
1320 Ft. from South Line of Section
4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5840
Name: Brandt Drilling Co., Inc.
City/State: Wichita, Kansas

Nearest lease or unit boundary line 660 feet
County Clark
Lease Name GABBERT Well # 11-24

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield X Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Ground surface elevation 1911 feet MSL
Domestic well within 330 feet yes X no
Municipal well within one mile yes X no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Depth to bottom of fresh water 150
Depth to bottom of usable water 200
Surface pipe by Alternate 1 X 2
Surface pipe planned to be set ±850

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 5/28/87 Signature of Operator or Agent J. Williams Title: Production Technician

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt.
This Authorization Expires 12-1-87 Approved By 6-1-87

Drilled

spud 6-3-87

Conductor - 73' of 20"
Surface - 253' of 13 3/8"
" - 801' of 8 5/8"

ww yes

Signature

D.G.

C. W/2 SW Sec. 24 Twp. 34 S, Rg. 24 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 400'-200' feet depth with 50 size of 60/40 Poz w/6% gel
2nd plug @ 50'-surface feet depth with 10 size of 60/40 Poz w/6% gel
3rd plug @ feet depth with size of
4th plug @ feet depth with size of
5th plug @ feet depth with size of
(2) Rathole with 10 size (b) Mousehole with 10 size

PUSHER Jack Kiser
TD 580' FORMATION
SURFACE PIPE 8 5/8" @ 801'
ANHYDRITE - ELEVATION 1911'
STARTING TIME & DATE 11:00 PM 6-15-87
COMPLETION TIME & DATE 2:30 AM 6-16-87
1st PLUG @ 810 FT. W/ 60 SX
2nd PLUG @ 40 FT. W/ 15 SX
3rd PLUG @ FT. W/ SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ Well to Future SX
CEMENT COMPANY B.G. Zitar
TECHNICIAN James R. Rose
60/40 Poz w/ 6% gel
RECEIVED STATE CORPORATION COMMISSION JUN 19 1987 CONSERVATION DIVISION Wichita, Kansas