

1 051457

7-23

API NUMBER 15- 025-20,894-0001

223 R

To: STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Operator: Kansas Petroleum, Inc.

Name &  
 Address 225 N. Market, Suite 310  
 Wichita, KS 67202

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 7 Year: 91

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4½" at 5686' w/175 sx cement, PBTD 5520', Perfs at 5501-05, 5489-92, 5459-62'

1st plug pump 20 sx cement and 2 sx hulls to perfs,

2nd plug pump 50 sx cement at 1100',

3rd plug pump 50 sx cement at 580',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None 

Operations Completed: Hour: 4 p.m. Day: 23 Month: 7 Year: 91

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 2 sx hulls,

2nd plug pumped 50 sx cement at 1100',

RECEIVED

3rd plug pumped 50 sx cement at 580',

STATE CORPORATION COMMISSION

4th plug pumped 10 sx cement at 40'.

JUL 25 1991

CONSERVATION DIVISION  
 Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 4002' of 4½" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional) observe this plugging.

DATE 8-8-91

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 32600