

1090010

7-28

API NUMBER 15-025-20,753-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 8, T 34 S, R 24 W/E

2190 feet from S section line

3140 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Gardiner Well # 1

Operator: Kansas Petroleum, Inc.

County Clark 185.25

Name & Address 225 North Market, Suite 310

Well Total Depth 5700 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 850

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 7 Year: 19 89

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 4 1/2" at 5699' PBD 5525' Perfs at 5477-79, 5486-90, 5499-5508'

1st plug pump 2 sx hulls and 25 sx cement at 5400',

2nd plug pump 50 sx cement at 880',

3rd plug pump 30 sx cement at 400',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Mike Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:30 p.m. Day: 28 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement at 5400',

2nd plug pumped 50 sx cement at 880',

3rd plug pumped 30 sx cement at 400',

4th plug pumped 6 sx cement at 40' - contractor will add last 4 sx cement when he

welds plate on wellhead.

RECEIVED
STATE CORPORATION COMMISSION
AUG - 1 1989

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pullers. Recovered 3030' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-3-89

Signed Michael A Wilson (TECHNICIAN)

WV. NO. 25533