

1 060782

API NUMBER 15- 175-20,896-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION app. W/2 NE SW, SEC. 26, T 34 S, R 34 W/8
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1980 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Mehl A Well # 1

Operator: Anadarko Petroleum Corp.
Name & Address: P. O. Box 351
Liberal, KS 67901

County Seward 218.56

Well Total Depth 6725 St. Louis feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1627

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address English Key Building, 333 E. English, Suite 215, Wichita, KS 67202

Company to plug at: Hour: 11:00 am Day: 26 Month: January Year: 19 86

Plugging proposal received from Jim Barlow

(company name) Anadarko (phone) 316-624-6253

Elevation 1635

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1600

1st plug on bottom with 50 sx cement

2nd plug at 3800' with 100 sx cement

3rd plug 50' in and 50' out of the surface pipe with 50 sx cement

4th plug at 800' with 40 sx cement

solid bridge - hulls - plug at 40' -- cement to surface with

5th plug 10 sx cement Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with 10 sx cement

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:00 pm Day: 26 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 6725' with 50 sx cement, 2nd plug at 3800' with 100 sx

cement, 3rd plug at 1642' with 50 sx cement, 4th plug at 800' with 40 sx cement, 5th &

6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with

10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION

Signed Paul A. Luthi (TECHNICIAN)

INVOICED observe this plugging.

DATE JAN 31 1986

INV. NO. 12202