


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Meade County. Sec. 19 Twp. 34S Rge. 29(W)  
Location as "NE/CNWKS" or footage from lines. Ctr NE NE  
Lease Owner Texaco Inc.  
Lease Name Adams O/A Well No. 1  
Office Address 614 Bitting Building, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed 12-1-1956  
Application for plugging filed 4-23-1969  
Application for plugging approved 4-24-1969  
Plugging commenced 4-26-1969  
Plugging completed 4-29-1969  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 7-20-1968  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves  
Producing formation Morrow Depth to top 5842 Bottom 5900 Total Depth of Well 6051 Feet  
Show depth and thickness of all water, oil and gas formations. PBTD 5986

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Gas	5842	5900	8-5/8"	1654'	None
				5-1/2"	5146'	2712'
				5-1/2"	911'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged as follows: 5986-5800 w/20 sxs cmt  
5800-900 w/hvy mud  
900-800 w/35 sxs cmt  
800-45 w/hvy mud  
45-surface w/15 sxs cmt.  
Comp 4 PM 4-29-69.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1969  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling Company  
Address Box 506, Liberal, Kansas 67901

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
M. R. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. R. Wilson  
614 Bitting Building, Wichita, Kansas  
(Address)

Subscribed and sworn to before me this 13th day of May, 1969



Peggy Sue Jones  
Notary Public.

RE: Adams # 1  
 C-NE-NE-19-3LS-29W  
 Meade County, Kansas  
 STATE CORPORATION COMMISSION  
 RECEIVED  
 APR 24 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

OPERATOR: The Texas Company  
 CONTRACTOR: An-Son Drilling Company  
 DRILLING SURFACE: 9-26-56  
 DRILLING COMPLETED: 10-30-56

FORMATIONS

Shale & Shells	0	-	701
Red Bed, shale	701	-	880
Red Bed, shale & gyp	880	-	1172
Shale, lime	1172	-	1326
Lime, shale	1326	-	1442
Lime, sand, shale	1442	-	1578
Hydrite	1578	-	1710
Shale, sand, lime	1710	-	1949
Shale, Shells	1949	-	2360
Shale, shells, lime	2360	-	2460
Shale, shells, lime stks.	2460	-	2535
Shale, lime	2535	-	2658
Shale, lime, sand	2658	-	2747
Shale, lime	2747	-	2814
Shale, sand, lime	2814	-	2880
Lime, sand	2880	-	2938
Shale, lime	2938	-	3015
Lime, shale, sand	3015	-	3073
Lime, shale stks.	3073	-	3160
Shale, Lime chalk	3160	-	3252
Shale, lime	3252	-	3293
Lime, shale stks.	3293	-	3420
Lime, chalk shale	3420	-	3429
Shale, lime	3429	-	3478
Shale, lime, chalk	3478	-	3599
Shale, Lime	3599	-	3735
Sandy lime, shale	3735	-	3847
Shale	3847	-	3979
Shale, lime	3979	-	4020
Lime Shale	4020	-	4168
Shale, lime	4168	-	4280
Shale, lime stks.	4280	-	4376
Shale lime	4376	-	4455
Lime shale	4455	-	4473
Lime	4473	-	4515
Lime, shale stks.	4515	-	4572
Shale, lime	4572	-	4601
Lime	4601	-	4704
Shale, lime	4704	-	4741
Lime	4741	-	4853
Shale, lime	4853	-	4910
Lime, shale stks.	4910	-	4951
Lime shale	4951	-	4967
Sandy Lime	4967	-	5019
Lime	5019	-	5074
Sand, shale, lime	5074	-	5136
Lime	5136	-	5190
Lime, shale	5190	-	5212
Shale, lime	5212	-	5240
Lime sand	5240	-	5257
Lime sand, shell	5257	-	5266
Shale, lime	5266	-	5309
Shale, sandy lime	5309	-	5325
Sandy shale, lime	5325	-	5392
Shale, lime	5392	-	5426
Lime, shale stks.	5426	-	5495

Shale, lime	5495	-	5562
Lime, shale stks.	5562	-	5731
Shale, lime	5731	-	5763
Shale, lime, sand	5763	-	5810
Sandy shale, lime	5810	-	5828
Shale, lime, sand	5828	-	5860
Sandy shale, lime	5860	-	5875
Sandy sand	5875	-	5907
Sand, shale, lime	5907	-	5925
Sandy shale, lime	5925	-	6025
Shale lime	6025	-	6051
TD	6051		

RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas