

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

16-34-29W

Meade County, Sec. 20 Twp. 34 Rge. 29 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE SW
Lease Owner Thomas & Brewer
Lease Name Adams Well No. 1-16
Office Address Box 1177, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed 3-15-61 1961
Application for plugging filed 5-22 1963
Application for plugging approved 5-22 (Oral) 1963
Plugging commenced 5-22 1963
Plugging completed 5-24 1963
Reason for abandonment of well or producing formation Non commercial



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production January 4 1963
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Morrow Depth to top _____ Bottom _____ Total Depth of Well 6051 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
5831-32	Morrow			8 5/8	1375	none
5836-37	"			4 1/2	5890	3127
5854-58	"					
5873-76	"					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 40 sx cement to plug off bottom perforations. Cement from 5566 to perforations at 5808-5814. Mud to 710' and 10' bridge. Pumped 35 sx. cement from 700' to 600' and mud to 50', 10' bridge and 15 sx. cement to base of cellar. Cut surface casing off 3 ft. below ground level and weld cap on same.

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargents Casing Pulling Service
Address 121 W. 9th St. Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.
Delvin P. Luck (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Delvin P. Luck
Box 1177, Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 1963

My commission expires 11-5-66

Madeline Kealey Notary Public.



THOMAS & BREWER
ADAMS #1-16

C/NE SW Section 16-34-29
Meade County, Kansas

R.T.D. 6051'

CONTRACTOR: Bennett & Roberts Drilling Co.

Commenced 1/20/61
Completed 2/13/61

Set 8 5/8" @ 1375' w/600' sx.
Set 4 1/2" @ 5890' w/125' sx.

Surface Soil	40
Sand & Clay	150
Clay & Shale	260
Sand	350
Red Bed & Sand	440
Red Bed	600
Red Bed & Sand	990
Red Bed & Shale	1252
Red Bed	1360
Anhydrite	1370
Anhydrite & Shale	1415
Red Bed & Shale	1900
Shale & Lime Streaks	2030
Shale, Lime & Anhydrite Streaks	2285
Lime & Shale	2540
Lime	2745
Lime & Shale	2860
Lime	3045
Lime & Chert	3096
Lime	3200
Lime & Chalk	3425
Lime 3485	3485
Lime & Chalk	3570
Lime	3740
Shale & Lime	3880
Lime	3994
Shale & Lime	4540
Lime	4685
Lime & Shale	4790
Lime	5465
Lime & Shale	5520
Lime	5585
Lime & Shale	5675
Lime	5730
Lime & Shale	5790
Lime	5842
Lime & Sand	5891
Lime	6051

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
RUSSELL COUNTY) SS.

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING COMPANY

By Madeline Beckey

Subscribed and sworn to before me this 14th day of February, 1961

My Commission Expires 6/17/62

Carroll Harrison
Notary Public