


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Meade County, Sec. 11 Twp. 34S Rge. 29W

Location as "NE/CNW/SW" or footage from lines Center SW-NW
Lease Owner Shenandoah Oil Corporation
Lease Name H. G. Adams "A" Well No. 1
Office Address 406 Mutual Savings Bldg., Ft. Worth, Texas 76102
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 24, 19 66
Application for plugging filed April 25, 19 66
Application for plugging approved April 26, 19 66
Plugging commenced April 24, 19 66
Plugging completed April 24, 19 66
Reason for abandonment of well or producing formation Drilled & Abandoned

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves
Producing formation None Depth to top - Bottom - Total Depth of Well 6500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------------|---------|------|----|--------|--------|------------|
| None Commercial | - | | | 8-5/8" | 1579 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud. Spotted 35 sx cement plug from 600-700', spotted 10 sx cement plug in top of 8-5/8" casing. Welded steel plate on top of 8-5/8" surface casing.

RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lohman-Johnson Drilling Company
Address Wichita, Kansas

STATE OF Texas, COUNTY OF Tarrant, ss.
Harold E. Burke (employee of owner) or () of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold E. Burke

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 66

My commission expires June 1, 1967

Mary D. Semmler
Notary Public.

D R I L L E R ' S L O G

COMPANY: Shenandoah Oil Corporation
 CONTRACTOR: Lohman-Johnson Drilling Company
 FARM NAME: H. G. Adams "A" Well No. 1
 LOCATION: C of SW-NW Section 11, T34S, R29W
 Meade County, Kansas

COMMENCED: April 2, 1966
 COMPLETED: April 23, 1966

| | | |
|------|------|-----------------------|
| 0 | 75 | Sand & shale |
| 75 | 820 | Sand, shale & red bed |
| 820 | 1510 | Shale, sand & gyp |
| 1510 | 1580 | Shale & anhydrite |
| 1580 | 1960 | Anhy, red bed & shale |
| 1960 | 2352 | Shale & anhy |
| 2352 | 2596 | Shale & sand |
| 2596 | 2987 | Shale, sand & lime |
| 2987 | 3149 | Lime & shale |
| 3149 | 3459 | Shale & lime |
| 3459 | 3730 | Lime |
| 3730 | 3935 | Lime & shale |
| 3935 | 4571 | Shale |
| 4571 | 4805 | Shale & lime |
| 4805 | 5214 | Lime |
| 5214 | 5288 | Lime & shale |
| 5288 | 5797 | Lime |
| 5797 | 5830 | Lime, shale & sand |
| 5830 | 6146 | Lime & shale |
| 6145 | 6500 | Total Depth Lime |

Set 8-5/8" new surface casing @ 1579 feet with 900 sacks cement.

I, Harold E. Burke, do hereby certify that the above and foregoing is a true and correct copy of the log of the H. G. Adams "A" #1 Well, located C/SW-NW Section 11, T34S, R29W, Meade County, Kansas as reflected by the records of Lohman-Johnson Drilling Company.

Harold E. Burke
 Harold E. Burke

STATE OF TEXAS X

COUNTY OF TARRANT X

Subscribed and sworn to and before me, a Notary Public, in and for Tarrant County, Texas, this 25th day May 1966.

Grace Benson
 GRACE BENSON

RECEIVED
 STATE CONSERVATION COMMISSION

MAY 26 1966

CONSERVATION DIVISION
 MEADE COUNTY, KANSAS