

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Well was completed on:
API NUMBER 15-189-20543-0000

LEASE NAME Rennick A

WELL NUMBER 2

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 35 TWP. 34S RGE. 35 ~~W~~(W)

COUNTY Stevens

Date Well Completed 8-15-81

Plugging Commenced 12-22-92

Plugging Completed 12-30-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 28, 1992 (date)

by Mr. Glenn Barlow of District 1 (KCC District Agent's Name).

Well was completed on:
Is ACO-1 filed? yes If not, Is well log attached? yes

Producing Formation Chester Depth to Top 6480 Bottom 6493 T.D. 6700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Chester	gas	6480	6493	8 5/8"	1656'	
				5 1/2"	6693'	2665'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP at 6410'. Put 2 sx cmt on top of plug. RIH w/ 2 3/8" tubing to 2666'. Pumped 80 sx cmt plug. Pulled up to 1674'. Pumped 50 sx cmt plug. Pulled up to 713. Pumped 40 sx cmt plug Pulled up to 40'. Set 10 sx cmt plug to surface. State witness: Mr. Glenn Barlow

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sartnets Casing Pulling Service License No. 6547

Address Liberal, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

VIC TUMLINSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 18th day of January **RECEIVED STATE CORPORATION COMMISSION**

My Commission Expires: 8-21-96

[Signature]
Notary Public
JAN 25 1993
CONSERVATION DIVISION
WICHITA, KANSAS
Revised 05-88