


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stevens County, Sec. 25 Twp. 34S Rge. 35 (W)
Location as "NE/CNW/SW" or footage from lines SE/4 NW/4
Lease Owner Barnett Oil Company
Lease Name Federal Well No. 1-25
Office Address 411 First Nat'l Bank Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 1, 19 68
Application for plugging filed June 4, 19 68
Application for plugging approved June 7, 19 68
Plugging commenced June 1, 19 68
Plugging completed June 1, 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 6650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1664'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 900'; used 1/2 sack of hulls and 35 sacks of cement to 800'; filled with mud to 45'; used 1/2 sack of hulls and 15 sacks cement to surface.

Cementing contractor: Sun Oil Well Cementing, Inc., Box 169, Great Bend, Kansas.

(Well Log attached)

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Michaelis Drilling Company
Address 211 No. Broadway, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James G. Gould, Partner of Barnett Oil Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James G. Gould
411 First Nat'l Bank Bldg., Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 4th day of June, 19 68

My commission expires February 27, 1972.

Mildred F. Willis
Notary Public.



FEDERAL NO. 1-25

WELL RECORD:

LOCATION:

C SE NW Section 25-34S-35W
Stevens County, Kansas

Commenced: 5-16-68
Completed: 6-2-68
(Rotary)

CONTRACTOR:

Graham-Michaelis Drilling, Inc.
Liberal Division
P. O. Box 1294
Liberal, Kansas 67901

CASING RECORD:

42 Joints 8-5/8" 24# Casing set
@ 1657' - Cemented w/600 sx Lt.
Wt. and 200 sx Common

LOG


Surface Sand & Red Bed	0 - 1214
Red Bed	1214 - 1653
Anhy	1653 - 1658
Anhy & Shale	1658 - 1860
Red Bed & Shale	1860 - 2409
Lime & Shale	2409 - 3709
Lime/Chalk & Shale	3709 - 3969
Lime & Shale	3969 - 4083
Lime	4083 - 4198
Lime & Shale	4198 - 4975
Lime, Chert & Pyrite/Shale	4975 - 5092
Lime & Shale	5092 - 5284
Lime & Chert	5284 - 5374
Lime & Shale	5374 - 5867
Lime & Shale	5867 - 5880
Shale	5880 - 5975
Lime & Shale	5975 - 6445
Lime	6445 - 6650

6650' - Total Rotary Depth

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1968
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Graham-Michaelis Drilling, Inc., Liberal Division, certifies that the above log is a true and correct copy of the formations encountered in drilling the above mentioned well, as taken from the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING, INC.
LIBERAL DIVISION

By 
H. R. Michaelis

HRM/rw

RECEIVED
JUN 10 1968
WICHITA, KANSAS