


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

HARPER County. Sec. 2 Twp. 3 4 S Rge. 9 E/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines SE SE
Lease Owner PICKRELL DRILLING CO.
Lease Name MARTIN Well No. 1
Office Address 205 Litwin Bldg., 110 N. Market, Wichita, Ks
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above
Section Plat

Gas
Date Well completed Aug. 28 1973
Application for plugging filed Sept. 22 1978
Application for plugging approved Sept. 23 1978
Plugging commenced Oct. 5 1978
Plugging completed Octo. 10 1978
Reason for abandonment of well or producing formation NOT PRODUCTIVE

If a producing well is abandoned, date of last production August 17, 1978

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well BILL OWENS
Producing formation Mississippi Depth to top 4532 Bottom Total Depth of Well 4537
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	268	None
				4 1/2	4517	3522

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

SAND FROM 4537 TO 4500. 4 Sacks cement from 4500 to 4470.

WOODEN BRIDGE AT 268. ROCK TO 260. 5 YARDS KREADY MIX.

RECEIVED
STATE CORPORATION COMMISSION

NOV - 2 1978

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CLARKE CORPORATION CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack Gurley, Engineer (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Gurley
110 N. Market, Suite 205, Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of November, 1978

My commission expires February 18, 1980

Jo Ann Sarver
Jo Ann Sarver Notary Public.



WELL LOG

W. J. Martin, I

2-34-96
Barber County, Kansas

Name of Operator: Barbara Oil Company
One First National Plaza
Suite 1650
Chicago, Illinois 60600

Date Completed: August 26, 1973

FROM	TO	
0	275	red bed
275	755	red bed and shale
755	1317	shale
1317	3760	lime and shale
3760	3820	sand
3820	4030	lime and shale
4030	4550	lime
4550		Total Depth

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1973

CONSERVATION DIVISION
Wichita, Kansas

SEAL OF BARBER COUNTY

COUNTY OF BARBER ss


Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Gary L. Hawk
Secretary

Subscribed and sworn before me this 4th day of September, 1973.

Mary Ann Schwamborn
Notary Public Barber County

My Commission Expires 7-10-77



DATE 8-11-78 WELL NO. 1 LEASE Martin FIELD Hibbard NE

ELEV.:
KB 1317
GL 11307

268' Base 8 7/8" 28# Csg w/2255x w/3% cc & 2% gel

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1978

CONSERVATION DIVISION
Wichita, Kansas

4537' Base 4 1/2" 10.5# K-SS Rq 2 w/1755x Common w/15% salt.
4549 LTD

4541 Base 2 3/8" EUE Tbg.