

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-077-20212-0000

LEASE NAME Martin #2 SWD

WELL NUMBER _____

SPOT LOCATION C SE NE

SEC. 2 TWP. 34 RGE. 9w (W) or (W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 7/18/84

Plugging Completed 7/23/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Production Co.

ADDRESS Box 333, Medicine Lodge, Ks. 67104

PHONE # (316) 886-5177 OPERATORS LICENSE NO. 5034

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4650 1/2'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	276'	none
				5 1/2"	4546'	3010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 2 hulls, 2 gel, 50 cement & plug to 4065'. Shot pipe at 3513' & 3010'.
Pulled 84 joints of pipe. Pumped 150 sacks cement 3% c.c. at 330'. Pulled rest of pipe.
94 joints total.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

AUG 01 1984

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1984



My Commission expires: _____

Notary Public

WELL LOG 15-077-20212-0000
Martin #2
SE NE 2-34-9W
Harper County, Kansas

Name of Operator: Barbara Oil Company
One First National Plaza
Suite 4650
Chicago, Illinois

Date Completed: September 30, 1973

<u>FROM</u>	<u>TO</u>		Casing Program	
0	310	Sand & red bed	8 5/8" 276'	225 Sacks Circulated
310	1148	Shale	5 1/2" 4546'	150 "
1148	3774	Lime and shale	This casing information furnished by Myers Engineering.	
3774	3845	Sand		
3845	4292	Lime and shale		
4292	4565	Lime		
4565		Total Depth		

R. Douglas Myers

STATE OF KANSAS

COUNTY OF BARTON ss


Gary L. Hawk, Secretary of Sweetman Drilling, Inc., being first duly sworn on oath says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Gary L. Hawk
Gary L. Hawk

Subscribed and sworn before me this 8th day of October, 1973.

Mary Ann Schramborn
Notary Public Barton County

My Commission Expires 7-10-77



RECEIVED
STATE CORPORATION COMMISSION

JUN 01 1984

CONSERVATION DIVISION
Wichita, Kansas