


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Harper County. Sec. 22 Twp 34 Rge. 9W (W)  
Location as "NE/CNW/SW" or footage from lines C NE SE  
Lease Owner Wm. Gruenerwald  
Lease Name Wilson "B" Well No. 2  
Office Address 35 E. Wacker Drive, Chicago, Illinois  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced \_\_\_\_\_ 19\_\_\_\_  
Plugging completed May 31, 19 61  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4649' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

T. D. 4649' - S. P. 8 5/8" - 231' - C W C - 5 1/2" 4648'  
P. B. 4612' - Top Perf. 4572'  
Bottom, sand to 4550' - 5 sacks cement - Pulled Pipe  
Mud to 220' - set R. B.  
R. B. 220' - 20 sacks cement  
R. B. 35' - 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Wilson Pipe Pulling  
Address Stafford, Kansas

STATE OF Illinois, COUNTY OF Cook, ss.  
WILLIAM GRUENERWALD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 14<sup>TH</sup> day of October, 1963

[Signature]  
Notary Public.

My commission expires 10-31-64

Wm. Gruenerwald  
#2 Wilson "B" (Cont.)

C NE SE  
22-34-9W  
Harper County, Kansas  
Page - 3 -

DRILLING PROGRESS  
(Midnight Daily)

12-29-59	Spud
12-30-59	Under Surface
12-31-59	1376
1-1-60	1895
1-2-60	2503
1-3-60	3018
1-4-60	3428
1-5-60	3920
1-6-60	4210
1-7-60	(Shut down repairs)
1-8-60	4527
1-9-60	4568
1-10-60	4650 T.D.

BIT RECORD

CP	E53	Retip	0-230
Hughes	OSC3	Retip	230-1253
Hughes	OSC		1253-1580
Security	M4N		1580-1860
Hughes	OWV		1860-2096
Hughes	OSC19		2096-2571
Hughes	OS119		2571-3054
Security	M4N		3054-3355
Hughes	OSCIG		3355-3820
Hughes	OWV		3820-4151
Hughes	OWL		4151-4271
Security	M4N		4271-4377
Security	M4N		4377-4580
Hughes	W7		4580-4650 TD

RECEIVED  
STATE CORPORATION COMMISSION

OCT 16 1963

CONSERVATION DIVISION  
Wichita, Kansas