

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-077-19053-0000  
API NUMBER 3-11-60

LEASE NAME Wilson

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

c-ne-se Ft. from S Section Line

Ft. from E Section Line

SEC. 22 TWP. 34 RGE. 9 (X) or (W)

COUNTY Harper

LEASE OPERATOR Clark Exploration

ADDRESS Box 245 Hardtner Ks. 67051

PHONE# (316) 296-4475 OPERATORS LICENSE NO. 09026

Date Well Completed 3-11-60

Character of Well SWD

Plugging Commenced 4-20-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-26-88

Did you notify the KCC District Office prior to plugging? yes

Which KCC Office did you notify? Wichita

Is ACO-1 filed? If not, is well log attached? no

Producing Formation Miss. Depth to Top T.D. 4650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	223	none
				4 1/2	4649	2900 junk

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand from 4620 to 4530 - 5 sx cement - dump Bailer - bridge - Pulled 4 1/2

Ran 3000 feet 2 3/8 spot 50 sx cement up to 2700 Pulled to 260 - spot 110 sx

class A cement cir. pulled tubing

BJ Pump

Vangessen and Elmo On Location

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105


Address Box 187 Medicine Lodge

STATE OF Kansas COUNTY OF Barber, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address)



SUBSCRIBED AND SWORN TO before me this 27 day of April, 1988

My Commission Expires: June 21, 1991