


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Harper County. Sec. 23 Twp. 34 Rge. 9 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines NW SW NW  
Lease Owner Wm. Grunerwald  
Lease Name C. R. East Well No. 1  
Office Address 35 Wacker Drive, Chicago, Illinois  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 4/24/59 19  
Application for plugging filed 6/16/59 19  
Application for plugging approved 6/10/59 19  
Plugging commenced 4/24/59 19  
Plugging completed 4/24/59 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eugene H. Graham  
Producing formation None Depth to top Bottom Total Depth of Well 1662 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	225.85'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 215' set bottom plug & 1/4 sack hulls w/15 sacks cement - Filled hole w/mud to 30' set top plug & 1/4 sack hulls w/8 sacks cement. Bridged rathole & cemented w/2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 18 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graham-Michaelis Drilling Company  
Address 211 North Broadway, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
O. W. Woodland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) O. W. Woodland  
211 N. Broadway, Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1959

T. J. Grier

Notary Public.

My commission expires January 7, 1961

PLUGGING  
FILE SEC. 23 T. 34 R. 9 W  
BOOK PAGE 43 LINE 12

EAST # 1

WELL RECORD:

LOCATION: C NW/4 SW/4 of NW/4 S. 1. 23-T34S-R5W Harper County, Kansas  
Commenced: 4/10/59  
Completed: 4/25/59  
(Rotary)

CONTRACTOR: Graham-Michaelis Drilling Company  
511 North Broadway  
Wichita 2, Kansas

CASING RECORD: 7 Joints of 5/8" Surface Casing cemented w/17% sk 2 1/2 cc

	LOG
Red Bed & Shale	0 - 635
Shale & Lime Streaks	635 - 1000
Shale & Lime	1333 - 2290
Shale & Lime Streaks	2290 - 2961
Shale & Lime	2961 - 3782
Shale & Sand	3782 - 3950
Shale	3950 - 4000
Shale & Lime	4000 - 4239
Lime	4239 - 4254
Shale & Lime	4254 - 4425
Lime	4425 - 4516
Shale & Lime	4516 - 4557
Lime	4557 - 4591
Lime & Chert	4591 - 4665

**RECEIVED**  
STATE CORPORATION COMMISSION  
JUN 18 1959  
CONSERVATION DIVISION  
Wichita, Kansas

4665' Total Rotary Depth

The undersigned, Graham-Michaelis Drilling Company, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

Graham-Michaelis Drilling Company

By John H. [Signature]  
Geologist

**PLUGGING**  
FILE SEC... 23T 34 R 9W  
BOOK PAGE... 49 LINE 42