


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stevens County, Sec. 23 Twp. 33 Rge. 38 (E) (W)
Location as "NE/CNW/SW" or footage from lines 1250' East & 660' South of Center
Lease Owner: Anadarko Production Company
Lease Name: Dunne-Hoffman "B" Well No. 2
Office Address: P. O. Box 351, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 25 1962
Application for plugging filed October 26 1962
Application for plugging approved 1962
Plugging commenced October 26 1962
Plugging completed October 26 1962
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation None Depth to top " Bottom " Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
NONE				8 5/8"	1723'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud. Spotted 150 sacks common from 2850' to 2400'; spotted 45 sacks common from 700' to 610'; spotted 15 sacks common from 40' to 5'.

RECEIVED
STATE CORPORATION COMMISSION
OCT 31 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Moran Brothers, Incorporated
Address 1200 Oil & Gas Building, Wichita Falls, Texas

STATE OF Kansas, COUNTY OF Seward, ss.
S. H. Neithercoat (employee of owner) or of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) S. H. Neithercoat

SUBSCRIBED AND SWORN TO before me this 29th day of October, 1962
Donald L. Vanjesson
Notary Public.

My commission expires
MY COMMISSION EXPIRES SEPT. 29, 1964

15-189-00041-0000

DRILLER'S LOG

WELL NAME Dunne-Hoffman "B" #2 COMPANY OPERATING Anadarko Production Company
 1250' East & 660' South of Center ADDRESS of COMPANY Box 351, Liberal, Kansas
 WELL LOCATION 1/4 1/4 1/4,
ft. North of South line,
ft. East of West line; Sec. 23 Twp. 33 Rge. 38, Stevens County, Kansas
 DRILLING STARTED October 6, 1962 DRILLING COMPLETED October 25, 1962
 WELL COMPLETED October 26, 1962 WELL CONNECTED _____, 19____
 ELEVATION 3157 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
NONE					

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8"	1723'	700	NONE

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Sand & Shells	0	371	Lime & Shale	5087	6249
Red Bed	371	1055	Lime & Sand	6249	6368
Red Bed & Sand	1055	1480	Lime	6368	6594
Red Bed & Gypsum	1480	1724	Total Depth	6594	
Red Bed & Anhydrite	1724	2135			
Shale & Anhydrite	2135	2545			
Shale & Lime	2545	4204			
Lime	4204	4283			
Lime & Shale	4283	4418			
Lime	4418	4720			
Lime & Shale	4720	4892			
Lime	4892	5087			

RECEIVED
 STATE CONSERVATION COMMISSION

OCT 21 1962

CONSERVATION DIVISION
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: NONE