

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 30 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-21541-0000

LEASE NAME LIGHT "U"

WELL NUMBER 1

990 Ft. from S Section Line

1520 Ft. from E Section Line

SEC. 29 TWP. 33 RGE 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 8-27-93

Plugging Commenced 9-10-98

Plugging Completed 9-14-98

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-25-98 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation L. MORROW Depth to Top 6173 Bottom 6190 T.D. 6650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L. MORROW	GAS	6173	6190	5-5/8"	1715	NONE
				5-1/2"	6317	2211

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. MIRU. PMP 2 SXS HULLS & 20 SXS CMT TO PLUG 6173'-5973'. CUT OFF 5-1/2" CSG @ 2211'. PMP 40 SXS CMT @ 2200' TO 2100'. POH TO 1740'. PMP 50 SXS CMT @ 1740' TO 1590'. POH TO 650'. PMP 40 SXS CMT @ 650' TO 550'. POH TO 40'. PMP 10 SXS CMT @ 40' TO 0'. CUT OFF AND CAP 8-5/8" CSG 4' BELOW GL. RDMO. STATE WITNESS: STEVE DURRANT.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 2nd day of Nov., 1998.

Shirley J Childers
 Notary Public

My Commission Expires: _____

