

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
10 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.C.R. - 82-3-117

API NUMBER 15-189=22030 00-00

LEASE NAME Bane Trust "B"

WELL NUMBER 1-31

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 31 TWP. 33S RGE. 38W (E) or (W)

COUNTY Stevens

Date Well Completed \_\_\_\_\_

Plugging Commenced 6-30-03

Plugging Completed 7-7-03

RECEIVED

JUL 17 2003

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR BEREDCO, INC.

ADDRESS P.O. Box 20380 Wichita, Kansas 67208

PHONE# (316) 265-3311 OPERATORS LICENSE NO. 5147

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on \_\_\_\_\_ (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 6396'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1766'	None
				4-1/2"	6395'	1120'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each sack. Set CT Bridge Plug @5910 with 2 sacks cement on top. Cut casing loose @1120', pulled up to 1000', pumped 30 sacks cement, pulled up to 650', pumped 10 sacks gel and 50 sacks cement, pulled up to 40' and circulated 15 sacks cement to surface. 60/40 pos. 6% gel.  
Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Beredco, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 15th day of July, 20 03

My Commission Expires: \_\_\_\_\_

