

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-189-22,096-0000

LEASE NAME COSTLEY "A"

WELL NUMBER 2

1980 Ft. from N Section Line

1980 Ft. from E Section Line

SEC. 32 TWP. 33S RGE 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 09/11/96

Plugging Commenced 03/11/97

Plugging Completed 03/11/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/25/97 (date)

by MR. STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW Depth to Top 6190' Bottom 6224' T.D. 6418'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW	GAS	6190'	6224'	8-5/8"	1675'	3'
				5-1/2"	6379'	2428'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU CP, PMPD 3 SXS HULLS & 25 SXS CMT, SET PLG 6190-5990', SHOT OFF 5-1/2" CSG @ 2428', CIRC HOLE W/9 PPG MUD, PMP 30 SXS CMT TO PLG 2400-2300', PULL 5-1/2" CSG TO 1700', PMP 50 SXS CMT TO PLG 1700-1550', PULL TO 650', PMP 40-SXS CMT TO PLG 650-550', PULL TO 40', PMP 10 SXS TO PLG 40-0', CUT OFF & CAP 8-5/8" CSG 3' BELOW GL. RESTORE LOCATION. KCC-REP NOTIFIED: STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 30th day of May, 1997

Shirley J. Childers
 Notary Public

My Commission Expires: 11/14/98

