

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,318-0000

LEASE NAME LOW "G"

WELL NUMBER 2

SPOT LOCATION C NW NW

SEC. 6 TWP. 33 RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 7/22/77

Plugging Commenced 3/29/85

Plugging Completed 4/3/85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Production Company

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District No. 1, Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Morrow Depth to top 5319 bottom 5327 T.D. 5440

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Saltwater	5319	5327	8-5/8"	1597'	None
				4-1/2"	5439'	3631'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Spot 1 sx hulls and 25 sx cmt 5327 to 5100. Cut off 4-1/2" at 3631'. Spot 50 sx cmt 2600' to 2500', 50 sx cmt 1650' to 1500'. Spot 35 sx cmt 600' to 500', 10 sx cmt 40' to 3'. Cut off 8-5/8" casing, cap well. Cement displaced with drilling mud.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547  
Address 620 South Lincoln, Liberal, Kansas 67901

RECEIVED

STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF LIBERAL, ss.

APR 19 1985

Paul Campbell (employee of operator) or  
~~(operator)~~ of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Paul Campbell

(Address) P. O. Box 351, Liberal, KS 67901

SUBSCRIBED AND SWORN TO before me this 18<sup>th</sup> day of April, 1985

BEVERLY J. WILLIAMS  
Seward County, Kansas  
My App. Exp. 11/21/86

Beverly J. Williams  
Notary Public

My Commission expires: November 21, 1986

Form CP-2 1-84  
Revised 06-83

