

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-129-20,167

LEASE NAME Santa Fe Trail Unit "A"

WELL NUMBER 2-1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1980 Ft. from S Section Line

1980 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 6 TWP. 33S RGE. 40 (NE) or (W)

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 10-30-74

Character of Well Input

Plugging Commenced 7-22-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7-24-92

The plugging proposal was approved on 7-21-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation Morrow Depth to Top 5354 Bottom 5378 T.D. 5546

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1606	0
				4 1/2	5546	2012

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circ hole w/mud. Pmp 10 sxs cmt on CIBP @ 5300-5250. TOH w/tbg. Pull free point. Shoot 4 1/2 csg @ 2012. Pmpd 50 sxs cmt @ 1656-1556. Pmpd 50 sxs cmt @ 800-700. Pmpd 15 sxs cmt @ 50-3. Cut off 8 5/8 csg 3' below ground level & cap. Rec 2012' 4 1/2 csg & 5305' 2 3/8 IPC tbg.

KCC witnessed. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6641

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Beverly J. Williams  
Beverly J. Williams, Eng. Tech.

(Address) P.O. Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 25th day of August, 19 92

Cheryl Steers  
Notary Public

My Commission Expires:



RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 25 1992  
CONSERVATION DIVISION  
WICHITA, KS