

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 30 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-129-20337-0000
 LEASE NAME GODDARD "A"
 WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

4628 Ft. from S Section Line
4720 Ft. from E Section Line
 SEC. 9 TWP. 33S RGE 40 (E) or (W)
 COUNTY MORTON
 Date Well Completed 12-6-77
 Plugging Commenced 10-12-97
 Plugging Completed 10-15-97

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION
 ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351
 PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549
 Character of Well GAS
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-21-97 (date)
 by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW "G" Depth to Top 5476' Bottom 5520' T.D. 5700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW G	GAS	5476'	5520'	8-5/8"	1525'	4'
				4-1/2"	5699'	1796'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRE POLE & PMP TRUCKS. MIX 2 SXS HULLS & 20 SXS CMT TO PLUG PERFS FROM 5476-5276. PLG WOULD NOT STAY DWN, HAD TO SHUT IN WELL. TH W/ 1 1/2 TBG. TAG CMT @ 5190. PULL 1 1/2 TBG TO 2946. MIX 20 SXS CMT TO PLUG ACROSS DV TOOL 2946-2746. WOC, TAG PLG @ 1400. TOH W/ 1 1/2 TBG. UNPACK CSG HEAD & FWLT 4 1/2" COLLAR ON 4 1/2" STUB. RU JACKS. SHOT 4 1/2" CSG OFF @ 1625. CIRC HOLE W/MUD & MIXED 60 SXS CMT TO PLG FROM 1625-1425. WOC, TAG PLG @ 1400 PULLED TO 550'. (CONTINUED ON BACK.)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Shawn D. Young
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 15th day of January, 1998

Shirley J. Childers
 Notary Public

My Commission Expires: _____



MIX 50 SXS CMT TO PLG FROM 550-400'. OH W/4 1/2" CSG, 48 JTS TOTAL. MIXED 10 SXS CMT TO PLG FROM 40 - 0'. LD OUT JACKS, CUT OFF & CAPPED 8 5/8" CSG 4' BELOW GL. RDMO POLE & PMP TRUCKS. WITNESSED BY KCC REP GARY WINTERS