

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-129-21196-00-00  
API NUMBER 15-129-21196

LEASE NAME Hayward "I"

WELL NUMBER 3

4620 Ft. from S Section Line

1830 Ft. from E Section Line

SEC. 10 TWP. 33S RGE. 40 (E) or (W)

COUNTY Morton

Date Well Completed 6-23-93

Plugging Commenced 1-21-94

Plugging Completed 1-25-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-17-94 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation None Depth to Top - Bottom - T.D. 5750

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1552	0
				5 1/2	5649	2312

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pmpd 2 sxs hulls & 25 sxs cmt plug from 5340-5140. Shot csg off @ 2312. Spot 30 sxs cmt plug from 2300-2200. Spot 50 sxs cmt from 1580-1430, spot 40 sxs cmt plug from 650-550. TOH w/csg & spot 10 sxs cmt plug from 40-0. Cut off 8 5/8 csg 3' below ground level & cap. KCC witnessed - Glenn Barlow. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent & Horton Plugging, Inc. License No. 31151

Address Rt 1, Box 49-BA, Tyrone, Oklahoma 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

Beverly J. Williams, Tech. Asst.

(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED  
KANSAS CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 14th day of February, 19 94

Cheryl Steers  
Notary Public

FEB 16 1994  
2-16-94  
CONSERVATION DIVISION  
WICHITA, KS  
Commission Expires:

