

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-21346-0000

LEASE NAME Shafer #1 Unit

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 4
2780 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 6 TWP. 33S RGE. 38 (E) or (W)

COUNTY Stevens

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444, Denver, Colorado 80217

PHONE# (303) 298-2770 OPERATORS LICENSE NO. 5208

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 6/24/89

Plugging Commenced 6/24/89

Plugging Completed 6/24/89

The plugging proposal was approved on _____ (date)
by Dodge City (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Morrow Depth to Top 5648' Bottom T.D. 6500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		GL		16"	74	0
		GL		8 5/8"	1726	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plug #1 2850-2575' w/100 sx Class H 60:40 Poz + 6% Col 13.37 ppg 1.57 cf/sx;
Plug #2 1750-1612' w/50 sx cmt; Plug #3 800-624' w/40 sx; Plug #4 40' - surf w/10 sx;
Rat hole w/15 sx; Mouse Hole w/10 sx; Jet and Cleaned pits.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Dowell - Schlumberger License No. _____

Address Box 887, Ulysses, KS 67880

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mobil Oil Corporation, 123 East 11th, Liberal, KS

67901

STATE OF Colorado COUNTY OF Denver, ss.

B. R. Maynard

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. R. Maynard

Regulatory Compliance Manager

(Address) P. O. Box 5444, Denver, CO 80217

SUBSCRIBED AND SWORN TO before me this 19th day of July, 19 89

My Commission Expires: 1/3/91

James George
Notary Public