

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-22391-0000

LEASE NAME WALKER "B"

WELL NUMBER 2

2310 Ft. from S Section Line

3300 Ft. from Section Line

SEC. 6 TWP. 33S RGE. 38 (E) or (W)

COUNTY STEVENS

Date Well Completed 7/28/2001

Plugging Commenced 7-28-2001

Plugging Completed 7-29-2001

RECEIVED
9-17-01
SEP 17 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

KCC WICHITA

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S. TAYLOR, SUITE 400, AMARILLO, TEXAS 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-28-2001 (date)

by MR. STEVE DURANT (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation NONE Depth to Top Bottom T.D. 6460

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 13-3/8" | 663' | NONE |
| | | | | 8-5/8" | 1771 | NONE |
| | | | | | | |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH W/4 1/2" DP TO 3100' & SPOT 100 SKS 60/40 POZMIX, 6%GEL @ 3100', TOH TO 1800' & SPOT 50 SKS, TOH TO 800' & SET 40 SKS, TOH TO 40' & SET 10 SKS FROM 40' TO 0'. SET 10 SKS IN MH & 10 SKS IN RH. CUT OFF 8-5/8" AND 13-3/8" CSG 3' BELOW GI AND CAP. PERMANENTLY INSCRIBE WELL NAME, NUMBER AND DATE PLUGGED ON CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor HALLIBURTON SERVICES License No. 5287

Address P.O. BOX 1598, LIBERAL, KANSAS 67905-1598

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.
L. MARC HARVEY, ENGINEERING TECHNICIAN III (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) L. Marc Harvey

L. MARC HARVEY, ENGINEERING TECHNICIAN III

(Address) 701 S. TAYLOR, SUITE 400, AMARILLO, TX, 79101

SUBSCRIBED AND SWORN TO before me this 12 day of September, 2001

Lori Pearson

Notary Public

My Commission Expires: 2/26/05

CR