

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 South Market Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-007-22567-0000

1998

LEASE NAME Donavan

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER 1

990 Ft. from N/S Section Line

2310 Ft. from E/W Section Line

LEASE OPERATOR Woolsey Petroleum

SEC. 10 TWP. 34 RGE. 13 ~~X~~ or (W)

ADDRESS 1966 SE Rodeo Drive, Medicine Lodge, KS 67104

COUNTY Barber

PHONE# 316 886-5606 OPERATORS LICENSE NO. 5506

Date Well Completed N/A

Character of Well Good

Plugging Commenced 12-9-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-10-98

The plugging proposal was approved on 12-9-98 (date)

by Kevin Strobe (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4634 Bottom 4638 T.D. 4737

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	220	None
				4 1/2	4770	4000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Set CIBP at 4600, dump 2sx cement, stretch and cut pipe at 4000, lay down casing. Allied pump 300 hulls, 10 jel, 50 cement, 10 jel, 100 hulls, 125sx cement. 60/40 6% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address 107 W. Fowler, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 10 day of December, 1998

Glenda Morrison

Notary Public

My Commission Expires: 11/30/04

9-2-99
A 11-53