


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plot

Meade County, Sec. 21 Twp. 34S Rge. (E) 29 (W)
Location as "NE/CNW/SW" or footage from lines SE, NE (1980' FN & 660' FE Lines)
Lease Owner: Pioneer Production Corporation
Lease Name: H. G. Adams Well No. 1
Office Address: P. O. Box 2542, Amarillo, Texas 79105
Character of Well (completed as Oil, Gas or Dry Hole): Gas
Date well completed: February 12 19 65
Application for plugging filed: July 13, 1970 19
Application for plugging approved: July 17, 1970 19
Plugging commenced: July 31, 1970 19
Plugging completed: August 5, 1970 19
Reason for abandonment of well or producing formation: excessive water production

If a producing well is abandoned, date of last production: October 19 69
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Ed Eves, Sublette, Kansas
Producing formation: Council Grove Depth to top: Bottom: Total Depth of Well: 3375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Gas & Water	3150	3375	7"	1370'	0
				2-7/8"	3370'	740'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
10 sacks of Cement were pumped to 3240'. 225 sx of Cement were mixed & pumped down Annulus space to 1370' 2-7/8" Casing was shot off at 740' and 35 sx of Cement was spotted between 650 and 800'. 10 sx of Cement was spotted from 0-40'.

RECEIVED
STATE CORPORATION COMMISSION
SEP 1 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Sargents Casing Pulling Services
Address: P. O. Box 506, Liberal, Kansas 67901

STATE OF Texas, COUNTY OF Potter, ss.
J.A. Tipton (employee of owner) or (owner-or-operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 2542, Amarillo, Texas 79105
(Address)

Subscribed and Sworn to before me this 27th day of August, 19 70

My commission expires 6-1-71
Charlotte Eaton
Notary Public.
CHARLOTTE EATON

CONTRACTOR'S WELL LOG

OWNER: AMARILLO OIL COMPANY
 CONTRACTOR: CHEMICAL & TECHNICAL SERVICES, INC.
 WELL: H. G. ADAMS # 1
 LOCATION: 1980' FNL & 660' FEL
 SEC. 21-34S-29W
 MEADE COUNTY, KANSAS
 COMMENCED: JANUARY 25, 1965
 COMPLETED: FEBRUARY 4, 1965

0	350	SAND
350	485	SAND & SHALE
485	1005	SHALE, SAND AND REDBED
1005	1365	REDBED AND SAND
1365	1370	ANHYDRITE
1370	1975	SHALE
1975	2275	SHALE, SALT AND LIME
2275	2606	SHALE AND LIME
2606	3063	LIME
3063	3100	CHERTY LIME
3100	3375	LIME
3375		ROTARY TOTAL DEPTH

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 17 1970
 CONSERVATION DIVISION
 Wichita, Kansas

SET 7" SURFACE CASING @ 1370' W/525 SACKS CEMENT

SET 2-7/8" PRODUCTION CASING @ 3370' W/125 SACKS CEMENT

WE HEREBY CERTIFY THIS TO BE A CORRECT AND ACCURATE LOG OF THE ABOVE DESCRIBED WELL, AS SHOWN ON THE DAILY DRILLING REPORTS.

CHEMICAL & TECHNICAL SERVICES, INC.

BY: [Signature]
ASST. TREASURER.

SUBSCRIBED AND SWORN TO BEFORE THIS 6 DAY OF FEBRUARY, 1965.

Donald Law
NOTARY PUBLIC