

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15- 175-20,565-0000

Operator's Full Name KENNEDY & MITCHELL, INC.

Complete Address 215 ONE TWENTY BLDG. WICHITA, KS. 67202

Lease Name MANHATTAN Well No. 44-708

Location C-NE-NE Sec. 14 Twp. 34 Rge. 32 (East) (West)

County SEWARD Total Depth 6510 FT.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor RAMCO DRILLING CO.

Address 200 DARDARE CTR.
100 SOUTH MAIN WICHITA, KS. License No. _____

Operation Completed: Hour: 2:30 PM Day: 12th Month: OCT Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

200st CLASS (4) CNT. 3% CA-CL.
8 5/8" - 1441^{FT} SP. CUL 600st HULLO LIGHT 2% GEL-3% CA-CL.

ORDERED 180st 50% FORTIX 4% GEL-3% CA-CL. + 8 5/8" PLUGS (2)
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st Plug. @ - 3000 FT 35st CNT.
2ND Plug. @ - 2800 FT 35st CNT.
3RD Plug. @ - 1420 FT 50st CNT. w/ Plug.
4th Plug. @ - 840 FT 40st CNT.
5th Plug SOLID BRIDGE @ 40^{FT} / 10st CNT. HULL'S PLUG
5st CNT. IN CNT HOLE + 5st CNT IN MOUSE HOLE.

I hereby certify that the above well was plugged as herein stated.

CEMENTED BY
HALLIBURTON CNT.

INVOICED

Signed: Wesley J. Schmidt
Conservation Division Agent

DATE 11-23-81

INV. NO. 8384-W

10-19-81
CONSERVATION DIVISION
Wichita, Kansas